



FAMILY RESOURCE CENTER - FRANKLIN, PA

PROJECT DESCRIPTION

The Family Resource Center replaced its originally specified steel with macro synthetic FORTA-FERRO fibers in a new construction in Franklin, PA. The total project was 80 cu yd and required a dosage of 3.0 lb/cu yd of macro synthetic FORTA-FERRO fibers. This was a typical slab-on-ground construction with a wood frame building on top, showing that **macro fibers can be a useful tool for smaller concrete contractors** as well. The fibers in this project allowed the contractor to **save a full day of placing and tying steel**, as well as making this **project more profitable now and in the future.**

KEY POINTS

- Easy to Mix
- Cost Savings
- Time Saving

DETAILS

Date: August 2018

Location: Franklin, PA

Dosage: 3.0 lbs/cu yd

Fiber: FORTA-FERRO® 2-1/4"

Contact us for more details