FORTA
FORTA-FERRO®

PROJECT PROFILE | PAVEMENT

MEADOWS VII WAREHOUSE FACILITY - FORSYTH COUNTY, GA

PROJECT DESCRIPTION

Fibers were specified for an exterior paving application of the truck dock and ramp at a 60,000 – 92,000 sq ft warehouse facility in Forsyth County, GA. FORTA-FERRO macro synthetic fibers were used at a dosage of 3.0 lb/cu yd in this pavement application that totaled 22,758 sq ft. FORTA-FERRO macro fibers were used to **add toughness and increase crack control.** Since this large facility has high volume traffic consistently picking-up and dropping-off loads, FORTA-FERRO was chosen to **increase the impact resistance and durability** of the paving slab. A broom finish was applied resulting in a **superior finish** with minimal surface fibers. **The contraction joints were very clean and do not show any raveling.**

KEY POINTS

- Increased Durability
- Reduced Cracking & Raveling
- Superior Finish

DETAILS

Date: 2019
Location: Forsyth County, GA
Dosage: 3.0 lb/cu yd
Fiber: FORTA-FERRO® 2-¼"

Contact us for more details