



## FARRINGTON HIGHWAY BUS PAD - WAIPAHU, HI

### PROJECT DESCRIPTION

Fibers were specified to reinforce the bus pad on Farrington Highway in front of Jack-In-The-Box in Waipahu, HI. FORTA-FERRO macro synthetic fibers were chosen to reinforce this slab-on-ground at a dosage of 7.5 lb/ cu yd. The county chose to use fibers to replace steel to help **save taxpayers money** while **increasing the durability** of the concrete. By replacing steel with fibers, the contractors were able to **save time** and **complete the project faster**.

### KEY POINTS

- Increased Durability
- Save Time
- Save Money

### DETAILS

**Date:** 2009

**Location:** Waipahu, HI

**Dosage:** 7.5 lb/cu yd

**Fiber:** FORTA-FERRO® 2-1/4"

Contact us for more details