



## DELIVERY SERVICE - CADILLAC, MI

### PROJECT DESCRIPTION

FORTA-FERRO macro synthetic fibers were used in the warehouse floor of a new delivery service location for upper Michigan located in Cadillac, MI. Fibers were used at a dosage of 5.0 lb/cu yd and placed via a Telebelt. Using **fibers allowed for a safer work environment** and **faster construction time** since there were no tripping hazards and no rebar or wire mesh needed tied or placed. FORTA-FERRO fibers also made the **floors more durable for heavy traffic**. This new warehouse allows timelier delivery by this company to the peninsula region of Michigan.

### KEY POINTS

- Safer Work Environment
- Increased Durability
- Faster Construction Time

### DETAILS

**Date:** September 2019

**Location:** Cadillac, MI

**Dosage:** 5.0 lb/cu yd

**Fiber:** FORTA-FERRO® 2-1/4"

Contact us for more details