



CALYPSO ENTERPRISES LLC. - ERIE, PA

PROJECT DESCRIPTION

A new growing and processing facility replaced specified wire mesh in a 50,000 sq ft slab-on-grade with a 3.0 lb/cu yd fiber dosage of FORTA-FERRO macro synthetic fibers. The ready mixer contacted FORTA a week before the first pour was scheduled because the architect wanted to see a wire mesh to fiber conversion. Using fibers allowed the ready-mix concrete producer to **tailgate the concrete instead of using a pump truck**. This allowed the **project to be finished quicker** and as a result, **saved the owner money**.

KEY POINTS

- Extend Joint Spacing
- Speed of Construction
- Replaced Steel Reinforcements

DETAILS

Date: January 2019

Location: Erie, PA

Dosage: 3.0 lb/cu yd

Fiber: FORTA-FERRO® 2-1/4"

Contact us for more details