FORTA
FORTA-FERRO®

PROJECT PROFILE

SLAB-ON-GROUND

MEYER'S DAIRY - LOGANTON, PA

PROJECT DESCRIPTION

Meyers Dairy in Loganton, PA recently chose FORTA-FERRO macro synthetic fibers to be used in a new slab-on-ground construction that will be used to store large silage bags. This project was 1,000 cu yd and used a dosage of 3 lb/cu yd of 2 1/4 in macro synthetic FORTA-FERRO fibers. They opted to to replace the specified 10 gauge 6 x 6 steel in the 50 x 120 slabs because the contractor wanted to tailgate the concrete rather than pump it. **By using fibers and tailgateing the concrete, time and money was saved** throughout the whole construction process. In addition this was the first project for either the contractor or the ready mixer to use macro synthetic fibers. **The job ran without a problem and the final finish was excellent.**

KEY POINTS

- Excellent Finish
- Save Time
- Cost Savings

DETAILS

Date: 2018
Location: Loganton, PA
Dosage: 3.0 lb/cu yd
Fiber: FORTA-FERRO® 2-¼"

Contact us for more details